SEPOY WIRING LTD. R.R. #2 LUCKNOW, ON N0G 2H0 519 529-3714

SEPOY WIRING LTD.

Huron Kinloss

Attention: John Yungblut

January 27, 2023

REF: Generator options for the Point Clark Pumping Station

Option #1 – **Diesel Generator**:

- supply one new 150 kw Diesel powered 347/600 volt 3 phase generator model DGVSW150STT3, enclosed, complete with safety shut downs, 200 amp main line breaker, 1500 w Kimhotstart engine heater and Deep Sea 7320 MKII Controller and battery charger
- CSA approved

supply a new 240 USG double wall subbase fuel tank with External Fill Spill box and vents, overfill alarm, rupture alarm and flexible fuel lines, factory TSSA. Fuel for site use and testing by others. Onsite fuel compliance inspection is Not included delivery of generator

supply and install a new 200 amp 600 volt Automatic Transfer Switch, rated NEMA 3R (outdoor)

- supply and installing of a new concrete pad, complete with excavation and removal of unused material
- Generator commissioning
- Wiring from the automatic transfer switch to the generator
- Wiring of engine heater and battery charger
- Removal of existing manual transfer switch
- labour
- shop supplies and materials
- ESA inspection fees

The cost of Option #1 is \$89 500.00 + HST.

Option #2 Natural Gas Generator:

- Supply and install a new 150 kw Natural Gas generator model #NPSWAS150STU, complete with safety shut downs, main line breaker, engine heater, battery charger, and enclosure,
- CSA approved
- Delivery of generator
- Commissioning of the generator
- Supply and install a new 200 amp 600 volt Automatic Transfer switch, rated Nema 3R
- Supply and installing of a new concrete pad, complete with excavation and removal of unused material
- Generator commissioning
- Wiring of the automatic transfer switch to the generator
- Wiring of engine heater and battery charger
- Labour

January 27, 2023 Page 2

- Shop supplies and materials
- ESA inspection fees
- **Please note** that no cost has been allowed for the Natural Gas hook up due to the uncertainty of the gas location at this time. Gas hook up would be over and above the estimate.

The cost of Option #2 is \$99 200.00 + HST (plus gas hook up)

Thank you for considering Sepoy Wiring LTD for this project. If you would like to proceed with one of the option as outlined above, please sign and scan this estimate back to

Yours Truly Rod Crich Master Electrician Sepoy Wiring LTD ECRA #7000753 January 27, 2023 Page 3