Water/Wastewater Budget – 2023 - Operating			
Project Name	Project Description	Alignment to Strategic Plan	
Lucknow Inflow and Infiltration \$30,000	Flow monitoring and closed-circuit video inspection at select locations in the Lucknow sanitary sewer system has been completed with few obvious sources of infiltration identified. More video inspections and repairs to some manhole structures that could be a source of infiltration is scheduled for 2023.		
Water/Wastewater	A third-party review of the operation and management of		
Operations Review	our water and wastewater systems will assist Township staff in determining what areas are working well and what		
\$20,000	needs improvement. In accordance with our Drinking		
+ -)	Quality Management Standard (DWQMS), the Operational		
	Plan is audited by a third party, however, this is only a		
	review of the Operation Plan and not a detailed review of all the components of our operations including policies,		
	procedure, organizational structure, etc.		
	We are planning to work with our consulting engineers, BM		
	Ross and Associates as well as a retired water and wastewater operations manager to undertake this review.		
	The findings that are produced will be valuable information		
	for Township staff to discuss with our Operating Authority		
	during contract negotiations. The current contract expires on June. 30, 2024 and we are planning to begin		
	discussions early in 2023.		
Lucknow Lift Pump	One of the three pumps in the Lucknow Sewage Pumping		
	Station has failed and is in need of replacement. Staff are		
\$40,000	planning to install a different model of pump that are considerably more expensive then the pump we were		
φ-0,000	using, but we are finding that the shorter lifespan of the		
	cheaper unit is not worth the cost savings.		

Water/Wastewater Budget – 2023 - Operating			
Project Name	Project Description	Alignment to Strategic Plan	
Ripley Lift Pump	We currently do not have a working spare pump at the Ripley Sewage Pumping Station, so we are looking to		
\$9,000	purchase a new spare pump in case one of the pumps fails.		

Water/Wastewater Budget – 2023 – Capital		
Project Name	Project Description	Alignment to Strategic Plan
Tanglewood &	This is the second and final phase of a street	
Ridgewood	reconstruction project in Point Clark. The first phase	
Watermains	included the reconstruction of Woodhaven Rd, a portion of	
	Tanglewood Dr. and Laidlaw Pl. This phase will include	
(Point Clark)	the remaining portion of Tanglewood Dr., Ridgewood Rd	
•	and Jardine PI. The existing 50mm (2") watermains have	
\$570,000	failed numerous times over the past few years and they	
	need to be replaced. The new watermains will be 150mm	
	(6") in diameter, fire hydrants will be installed and water	
	services will be replaced.	
Point Clark Well 2	The last video inspection of Well 2 in Point Clark was in	
Inspection	2012 so it is overdue for another inspection. Drinking	
	water wells are typically inspected every 10 years.	
\$15,000		
Murdoch Glen	One of the high lift pumps at the Murdoch Glen pumping	
Pump Repairs	house in the Heritage Heights area is leaking and will need	
<b>\$10,000</b>	to be rebuilt.	
\$12,000		
Ripley	The Ripley Wells 3 and 4 investigation is scheduled to	
Contamination	continue in 2023 with the inspection of the well casings to	
/Inspection	determine if there is any source of a leak that could not be	
\$30,000	detected in the pressure test conducted in 2022.	

Water/Wastewater Budget – 2023 – Capital			
Project Name	Project Description	Alignment to Strategic Plan	
Ripley Well 1	If the Ripley Well 3 and 4 raw water contamination issue is		
Abandonment	resolved in 2023, staff are planning to abandon the original		
\$20,000	well in Ripley that is located south of the Ripley & District		
	Fire Station. This will leave Ripley with three operating		
	drinking water wells which is more than adequate for this		
	system.		
Ripley Well 2 MCC	The Master Control Centre (MCC) at Ripley Well 2 is in		
Replacement	need of replacement.		
(\$160,000)			
Ripley Well 2	Ripley Well 2, which is located directly east of Well 1, is		
Inspection	due for a video inspection to evaluate its condition. The		
(\$15,000)	well was last inspected in 2013.		
Lucknow Well 5	This project will provide redundancy in the Lucknow water		
VFD and Mag	system in the event that the Lucknow Standpipe has to be		
Meter	decommissioned before the new elevated tank is		
	commissioned or when the new tower is taken offline for		
\$35,000	maintenance or inspection purposes. The new controls will		
	be able to regulate water pressure across the system		
	without elevated storage.		
	This project was proposed to begin in 2022, however, staff		
	decided to delay this until the new PTTW amended was		
	approved by the MECP.		

OTHER	