



June 19th, 2023

Lucknow District Fire Department
PO Box 580, Lucknow, Ontario, N0G 2H0

Fire Chief Chris Cleave,

Thank you for the opportunity to provide you with a formal quote on a custom-built Dependable pumper mounted on a Spartan FC-94 chassis as per your request. Dependable Emergency Vehicles produces high-quality, cost-effective emergency vehicles that have been proven in the emergency response industry for over 40 years. From conception, to building and delivery, Dependable is able to support you throughout the acquisition process, and during the entire lifetime of the vehicle. We look forward to the opportunity to work with you and your department in delivering a high-quality apparatus which has been "DESIGNED TO PERFORM, BUILT TO LAST" for many years to come.

Supply One (1) Dependable Pumper mounted on a Spartan FC-94 Chassis

#58043 \$599,999.00 + HST

Included:

- Ontario PMCVI inspection
- FOB: Brampton, Ontario

Optional Items:

- Supply and install one (1) FoamPro 2001 foam proportioning system. Discharges will be as follows: 1x front bumper discharge, 1x crosslay/speedlay, 1x crosslay/speedlay, *** optional 1x rear discharge **\$24,130.00 + HST**
- One (1) 2.5" discharge preconnect to the front of the right side of the hosebed. The valve shall be electric to accommodate the additional discharge on the pump panel. **\$13,998.00 + HST**
- Supply and install eleven (11) adjustable shelves. The shelf will be made out of AP.1885052H32 aluminum plate with a formed 2" edge on all sides. The shelf will be sanded finish and include CPI SS0001-4 shelf-supports to mount it on the Unistrut channels. The shelf shall include black turtle tile. Locations to be as follows two (2) in L1, one (1) in L2, two (2) in L3, two (2) in R1, one (1) in R2, two (2) in R3 and one (1) in B1 compartment. **\$ 8,876.00 + HST**
- Five (5) full-depth (approximately 25" deep) roll-out trays shall include Faucher LH/RH aluminum slide mechanisms, with trays that shall be made out of AP.1885052H32 aluminum plate with a formed 3" edge on all sides. The full-depth roll-out trays shall include a smooth sanded finish. The full-depth roll-out trays shall include 3M 983-72-2 2" red reflective tape all available edges. The full-depth roll-out trays shall include welded closed corners with drilled drainage holes. Tray shall include black turtle tile. Locations to be as follows: L1/L3/R1/R3/B1 Compartments. **\$3,800.00 + HST**
- Supply and install one (1) 2.5" discharge to the pump panel. Location to be in best fit position on the driver side pump panel. **\$6,795.00 + HST**

***Please note: This quote is valid for 15 days. The estimated delivery date of this apparatus is to be determined as the chassis is in stock however it is on a first come first serve basis and only a firm purchase order will secure the chassis. A 30% deposit is required on order, balance is due on pickup of the apparatus.

If you have any further questions or concerns, please don't hesitate to contact me.

Thank you,

Pino Natale

Pino Natale
Director of Emergency Vehicles Division | 416-561-6724 | pino@dependable.ca